

Part B - General Requirements for Pump Test

1.4 The yield of each proposed independent on-site **Ground Water** source should be tested as follows:

- a) the yield of the **Well** should be tested by a **Qualified Well Driller** or a **Qualified Pump Installer**, who will be required to submit **Well** reports and water quality results to the **Regional District** and to the Comptroller of Water Rights
- b) testing should be conducted at the location labeled "Point of Testing" on Figure B.3;
- c) testing should occur during the period from August of one year to April of the following year;
- d) all tests should be performed at a rate of at least 3.8 litres per minute for a period of at least 24 hours and a minimum of 2,275 litres per day, unless a **Qualified Professional** specifies a greater or lesser rate, or for a longer period, that reflects **MDD** and duration in order to adequately assess the sustainability of the source for the intended use of the proposed subdivision and to evaluate long-term drawdown interference, in which case testing must be performed at the rate and duration specified by the **Qualified Professional**; and
- e) where a subdivision will result in the development of three or more **Parcels** that are not each at least 2 hectares in area, the **Qualified Professional**, if required, should undertake a brief step test at each **Well** prior to undertaking 24 hour constant-discharge tests.